Newhaven Estate - Stage 15, Tarneit

Level 1 Inspection & Testing Report

Reference: 1120 0303-1

Prepared for:

BMD Urban

May 2022

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Document Control Record

Prepared by:
A&Y Associates Pty Ltd
ABN 92 614 244 665
5/16 Network Drive
Truganina, VIC 3029
T: (03) 8754 8325
E: info@ayassociates.com.au
W: www.ayassociates.com.au

Document control

Report title		Level 1 Inspection & Testing			
Project reference number		1120 0303-1			
Client		BMD Urban			
Contact name		Luke Bett			
Contact number		0428 967 392			
Contact e-mail		Luke.Bett@bmd.com.au			
Revision	**Date**	**Descriptions/Status**	**Author**	**Reviewer**	**Approver**
0	**19/05/2022**	**First Issue**	**B Mu**	**A Tan**	**A Tan**

Approver

Alvin Tan

(BE Civil and Infrastructure), MIEAust

Senior Geotechnical Engineer

E: alvin@ayassociates.com.au | M: 0449 288 338

ENGINEERS
AUSTRALIA
Professional Engineer
MEMBER

Disclaimer

The findings and conclusions contained in this report are made based on site conditions that existed at the time this work was conducted. The conclusions present in this report are relevant to the conditions of the site and the state of legislation currently enacted as at the date of this report.

Findings and conclusions are made assuming that the soil, groundwater, geological and chemical conditions detailed within this report are accurate and remain applicable to the site at the time of writing. No other warranties are made or intended.

A&Y Associates (A&Y) Pty Ltd has used a degree of skill and care ordinarily exercised by reputable members of our profession practicing in the same or similar locality.

A&Y does not make any representation or warranty that the conclusions in this report will be applicable in the future as there may be changes in the condition of the site, applicable legislation or other factors that would affect the conclusions contained in this report.

This report has been prepared exclusively for use by our client. This report cannot be reproduced without the written authorisation of A&Y and then can only be reproduced in its entirety.

Applicability

This report has been prepared for the benefit for our client with respect to the particular brief given to us and it may not be relied upon in other contexts or for any other purpose without our prior review and agreement.

No responsibility for this report will be taken by A&Y if it is altered in any way, or not reproduced in full.

Contents

1 Introduction

This report presents the results of the Level 1 Inspection and Testing for the construction of the fill platforms located in Newhaven Estate - Stage 15, Tarneit.

2 Project Summary

It is understood that BMD Urban require the fill platforms within Newhaven Estate - Stage 15, Tarneit, to be constructed under Level 1 Inspection and Testing undertaken by a Geotechnical Inspection and Testing Authority (GITA).

Level 1 Inspection and Testing, as defined in AS3798-2007 "Guidelines on Earthworks for Commercial and Residential Development," provides for full time inspection of the construction of controlled fill and field and laboratory testing in accordance with AS1289 "Methods of Testing Soils for Engineering Purposes".

The Level 1 inspection was undertaken by a Geotechnician from A&Y Associates over a period of eight (8) working days from the **17th of January 2022 to 4th of April 2022**.

This report is applicable for fill placed by BMD Urban for the following lots located in Newhaven Estate - Stage 15, Tarneit, as shown in Appendix A – Site Plan.

- Lot 1501 – 1506
- Lot 1508 – 1537

3 Project Specifications

Specifications on the compaction and moisture requirement have been provided for the construction works in Newhaven Estate - Stage 15, Tarneit. Based on report (ref: G3228.1 AA prepared by GroundScience PTY LTD) all filling on lots and within road reserves greater than 200mm is to be undertaken under level 1 supervision in accordance with AS3798. The supervision and inspections were performed based on AS3798. A short summary of the requirements outlined in the geotechnical investigation report and AS3798 is provided below:

- Material to be used for fill construction shall satisfy the requirements of AS3798-2007 "Guidelines on Earthworks for Commercial and Residential Developments". The material used shall be free of:
    - Organic soils, such as topsoils, severely root affected subsoil and peat;
    - Contaminated soils;
    - Materials that undergo volume change or loss of strength when disturbed and exposed to moisture;
    - Silts, or materials that have deleterious engineering properties of silt;
    - Fill that contains wood, metal, plastic, boulders, or other deleterious material, in sufficient proportions to affect the required performance of fill;
    - The maximum particle size of any rocks or other lump, within the layer, has not exceeded two-thirds (2/3) of the compacted layer thickness.
- The fill shall be compacted to a density ratio of not less than 95% Standard (AS 1289 5.1.1or 5.7.1and 5.8.1, 5.4.1) and 98% Standard in the top 0.3m in all areas.
- Fill must be moisture conditioned to a moisture ratio between 90% and 110% of standard compaction.
- The fill material shall not contain greater than 20%, by volume, of rock particles coarser than 37.5mm and no rock particle or soil clod over 150mm in any dimension.

4 Subgrade Assessment

The subgrade was assessed by A&Y Associates following the topsoil removal and before any fill was placed. The subgrade assessment was undertaken on the **17th January 2022, 28th March 2022 and 4th April 2022** as mentioned in report *1120 0303-1 (SSI1)*.

The exposed subgrade material comprised natural silty clay. No wet or soft patches were found during the inspection. No evidence of deleterious material was found during the inspection.

5 Earthworks

The earthworks for this project included stripping of topsoil, removing of tree roots, proof rolling the subgrade and placement and compaction of fill to construct engineered platforms.

Based on design plans and site inspection, it appears that the fill thickness placed is approximately 200mm-400mm. The fill layers or thickness nominated in this report are provided as a guide on the amounts of fill placed and do not necessarily reflect an accurate survey of the fill levels.

6 Fill Material

The fill material used for the platform consisted of site derived material. The material was predominantly comprised of Silty Clay with gravel.

7 Testing

Field density testing was undertaken on the compacted fill at a frequency of a minimum of 3 tests per lot (AS3798 Table 8.1).

Tests were performed using a Nuclear Density Gauge for field density determination as per AS 1289.5.8.1. Testing was completed at a minimum rate of 3 field density tests per day's production based on the minimum requirements of AS 3798-2007 and taken from each layer of fill placed.

A total of 24 field density tests were performed during the earthworks. All of the test results met the specified compaction requirement of 95% Standard Compaction and 98% Standard in the top 0.3m in all areas.

The locations of the 24 field density tests are shown in Appendix B – Test Locations. A summary of the test results obtained from the field density testing is presented in Appendix C – Test Results Summary. The laboratory test reports of the field density tests are presented in Appendix D – NATA Test Results.

8 Finished Surface Levels

It should be noted that even though the final fill layer meets the specification requirements, over time, the material may be subject to adverse weather conditions resulting in either surface softening or drying and cracking. The top 150mm – 200mm of the fill will deteriorate with time and should be considered by the foundation engineer.

9 Exclusion

A&Y Associates was not involved in monitoring and testing the following works and as such are not included in the Level 1 report.

- Any trenches excavated and backfilled on site for the installation of underground services such as sewers, electrical conduits, water mains etc.
- Footpaths in front of the lots that may be excavated and filled after the Level 1 supervision conducted by A&Y Associates.
- Uncontrolled fill and topsoil that may have been placed as part of the landscaping of the site following the completion of the engineered fill construction.

10 Conclusion

On the completion of the earthworks and after analysing the materials used, it has been concluded that the filling procedure conducted by BMD Urban appears to be consistent with the requirements of AS 3798 in regards to the placement of fill materials on a project under Level 1 Supervision and in accordance with the project specification as provided to A&Y Associates.

Appendix A - Site Plan

Area Inspected and Tested

PROJECT: Newhaven Estate – Stage 15 (Level 1)	**CLIENT:** BMD Urban	**SITE PLAN SKETCH—NOT TO SCALE**	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION: Tarneit	**PROJECT No:** 1120 0303-1		

Appendix B – Test Locations

Indicative Test Location

PROJECT: Newhaven Estate – Stage 15 (Level 1)	**CLIENT:** BMD Urban	SITE PLAN SKETCH—NOT TO SCALE	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION: Tarneit	**PROJECT No:** 1120 0303-1		

Appendix C – Test Results Summary

Project No	1120 0303-1				Client	BMD Urban				
Project Name	Newhaven Estate - Stage 15				Specification			Density Ratio ≥ 98% of Peak Wet Density		
Location	Tarneit									
Test No	Retest of Test	Date	Location	Layer	Oversize	Density Ratio	Moisture Ratio	Moisture Variation	Pass / Fail	Retest
#	#		Lot #	#	%	%	%	%		Pass / Fail
1	-	17/01/2022	-	1	6.5	98.5	98.0	-0.5	Pass	-
2	-	17/01/2022	-	1	5.0	99.0	96.5	-0.5	Pass	-
3	-	17/01/2022	-	1	5.0	99.0	97.0	-1.0	Pass	-
4	-	18/01/2022	-	FSL	6.0	98.5	96.0	-0.5	Pass	-
5	-	18/01/2022	-	FSL	5.0	98.0	97.0	-0.5	Pass	-
6	-	18/01/2022	-	FSL	6.3	98.5	98.5	-0.5	Pass	-
7	-	19/01/2022	-	1	3.0	98.5	95.5	-1.0	Pass	-
8	-	19/01/2022	-	1	4.0	98.5	97.5	-0.5	Pass	-
9	-	19/01/2022	-	1	2.0	98.0	96.0	-1.0	Pass	-
10	-	20/01/2022	-	1	4.0	98.5	97.0	-0.5	Pass	-
11	-	20/01/2022	-	1	4.3	98.5	98.5	-0.5	Pass	-
12	-	20/01/2022	-	1	3.8	99.0	103.5	1.0	Pass	-
13	-	21/01/2022	-	FSL	4.0	98.5	98.5	-0.5	Pass	-
14	-	21/01/2022	-	FSL	6.0	98.0	96.5	-0.5	Pass	-
15	-	21/01/2022	-	FSL	4.5	98.0	97.5	-0.5	Pass	-
16	-	28/03/2022	-	FSL	0.0	99.0	107.0	2.0	Pass	-
17	-	28/03/2022	-	FSL	0.0	99.0	108.0	2.0	Pass	-
18	-	28/03/2022	-	FSL	0.0	99.0	107.5	2.0	Pass	-
19	-	29/03/2022	-	FSL	0.0	99.0	97.0	-0.5	Pass	-
20	-	29/03/2022	-	FSL	0.0	99.0	98.5	-0.5	Pass	-
21	-	29/03/2022	-	FSL	0.0	99.0	99.0	-0.5	Pass	-
22	-	4/04/2021	-	FSL	0.0	99.0	96.0	-0.5	Pass	-
23	-	4/04/2021	-	FSL	0.0	101.0	97.5	-0.5	Pass	-
24	-	4/04/2021	-	FSL	0.0	99.0	99.0	-0.5	Pass	-
** Negative (-) value indicates that the field moisture content is drier than the optimum moisture content (OMC)										
** Positive (+) value indicates that the field moisture content is wetter than the optimum moisture content (OMC)										

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Appendix D – NATA Test Results

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	1	
Location:	Tarneit					

Sample No		1	2	3			
Date Tested		17/01/2022	17/01/2022	17/01/2022			
Time Tested		PM	PM	PM			
Test Location		Refer to Plan	Refer to Plan	Refer to Plan			
Level/Layer		Layer 1	Layer 1	Layer 1			
Layer Thickness	mm	150	150	150			
Test Depth	mm	125	125	125			
Field Wet Density	t/m^3	1.87	1.89	1.87			
Field Moisture Content	%	23.0	22.7	22.8			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	6.5	5.0	5.0			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.87	1.89	1.87			
Optimum Moisture Content	%	23.5	23.5	23.5			
Moisture Ratio	%	98	96.5	97			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	-1.0 Drier			
Density Ratio	%	98.5	99.0	99.0			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI01)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory:

David Burns

Date: 24/01/2022

PROJECT: Newhaven Estate – Stage 15 (Level 1)	**CLIENT:** BMD Urban	**DATE:** 17/01/2022	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION: Tarneit	**PROJECT No:** 1120 0303-1 (SI01)	**SITE PLAN SKETCH—NOT TO SCALE**	

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	2	
Location:	Tarneit					

Sample No		4	5	6			
Date Tested		18/01/2022	18/01/2022	18/01/2022			
Time Tested		PM	PM	PM			
Test Location		Refer to Plan	Refer to Plan	Refer to Plan			
Level/Layer		FSL	FSL	FSL			
Layer Thickness	mm	200	200	200			
Test Depth	mm	175	175	175			
Field Wet Density	t/m^3	1.90	1.87	1.85			
Field Moisture Content	%	24.1	24.8	24.6			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	6.0	5.0	6.3			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.90	1.89	1.85			
Optimum Moisture Content	%	25	25.5	25			
Moisture Ratio	%	96	97	98.5			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	-0.5 Drier			
Density Ratio	%	98.5	98.0	98.5			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI02)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory:

David Burns

Date: 24/01/2022

N

Test Location

PROJECT:	CLIENT:	DATE:	
Newhaven Estate – Stage 15 (Level 1)	BMD Urban	18/01/2022	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION:	PROJECT No:		
Tarneit	1120 0303-1 (SI02)	SITE PLAN SKETCH—NOT TO SCALE	

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	3	
Location:	Tarneit					

Sample No		7	8	9			
Date Tested		19/01/2022	19/01/2022	19/01/2022			
Time Tested		PM	PM	PM			
Test Location		Lot #1515 Refer to Plan	Lot #1517 Refer to Plan	Lot #1519 Refer to Plan			
Level/Layer		Layer 1	Layer 1	Layer 1			
Layer Thickness	mm	200	200	200			
Test Depth	mm	175	175	175			
Field Wet Density	t/m^3	1.90	1.86	1.92			
Field Moisture Content	%	22.5	24.9	23.5			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	3.0	4.0	2.0			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.92	1.88	1.95			
Optimum Moisture Content	%	23.5	25.5	24.5			
Moisture Ratio	%	95.5	97.5	96			
Moisture Variation from OMC	%	-1.0 Drier	-0.5 Drier	-1.0 Drier			
Density Ratio	%	98.5	98.5	98.0			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI03)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory:

David Burns

Date: 31/01/2022

PROJECT: **Newhaven Estate – Stage 15 (Level 1)**	**CLIENT:** **BMD Urban**	**DATE:** **19/01/2022**
LOCATION: **Tarneit**	**PROJECT No:** **1120 0303-1 (SI03)**	**SITE PLAN SKETCH—NOT TO SCALE**

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client: BMD Urban **Job No:** BMD2032

Project: Newhaven Estate - Stage 15 (Level 1) **Report:** 4

Location: Tarneit

Sample No		10	11	12			
Date Tested		20/01/2022	20/01/2022	20/01/2022			
Time Tested		PM	PM	PM			
Test Location		Lot #1514 Refer to Plan	Lot #1512 Refer to Plan	Lot #1510 Refer to Plan			
Level/Layer		Layer 1	Layer 1	Layer 1			
Layer Thickness	mm	200	200	200			
Test Depth	mm	175	175	175			
Field Wet Density	t/m^3	1.86	1.88	1.91			
Field Moisture Content	%	23.7	25.1	24.3			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	4.0	4.3	3.8			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.87	1.89	1.91			
Optimum Moisture Content	%	24.5	25.5	23.5			
Moisture Ratio	%	97	98.5	103.5			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	1.0 Wetter			
Density Ratio	%	98.5	98.5	99.0			

Specification: 98% STD **Test Selection:** N/A

Notes: Ref : 1120 0303-1 (SI04)

Test Method AS1289 5.8.1, 5.7.1, 2.1.1, 1.1 **Sampling Method:** AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory: David Burns

Date: 31/01/2022

N

Test Location

Rev	Amendments	Approved	Date
D	ISSUED FOR CONSTRUCTION	M.H.	04/10/21
B	OVERLAND FLOW PATH AND TREE RINGS ADDED	M.H.	01/10/21
A	ISSUED FOR APPROVAL	M.H.	26/08/21

spiire
414 LA TROBE STREET PO BOX 16084 MELBOURNE VICTORIA 8007 AUSTRALIA T 61 3 9993 7555
spiire.com.au ASN 55 050 029 635

PEET

Designed	Checked
P.CLIFTON	J. KOEHLER
Authorised	Date
M.HOLMES	26/08/21

NEWHAVEN ESTATE
STAGE 15
ROAD AND DRAINAGE
FACE PLAN
WYNDHAM CITY COUNCIL
PEET NO.1895 PTY LTD
CONSTRUCTION 303447CR200 0

PROJECT:	CLIENT:	DATE:	
Newhaven Estate – Stage 15 (Level 1)	BMD Urban	20/01/2022	
LOCATION:	PROJECT No:	SITE PLAN SKETCH—NOT TO SCALE	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
Tarneit	1120 0303-1 (SI04)		

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	5	
Location:	Tarneit					

Sample No		13	14	15			
Date Tested		21/01/2022	21/01/2022	21/01/2022			
Time Tested		PM	PM	PM			
Test Location		Lot #1516 Refer to Plan	Lot #1518 Refer to Plan	Lot #1520 Refer to Plan			
Level/Layer		FSL	FSL	FSL			
Layer Thickness	mm	200	200	200			
Test Depth	mm	175	175	175			
Field Wet Density	t/m^3	1.88	1.90	1.81			
Field Moisture Content	%	24.1	25.6	24.9			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	4.0	6.0	4.5			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.89	1.92	1.83			
Optimum Moisture Content	%	24.5	26.5	25.5			
Moisture Ratio	%	98.5	96.5	97.5			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	-0.5 Drier			
Density Ratio	%	98.5	98.0	98.0			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI05)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory:

David Burns

Date: 31/01/2022

N

Test Location

PROJECT: Newhaven Estate – Stage 15 (Level 1)	**CLIENT:** BMD Urban	**DATE:** 21/01/2022
LOCATION: Tarneit	**PROJECT No:** 1120 0303-1 (SI05)	**SITE PLAN SKETCH—NOT TO SCALE**

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	6	
Location:	Tarneit					

Sample No		16	17	18			
Date Tested		28/03/2022	28/03/2022	28/03/2022			
Time Tested		PM	PM	PM			
Test Location		Lot #1503 Refer to Plan	Lot #1504 Refer to Plan	Lot #1506 Refer to Plan			
Level/Layer		FSL	FSL	FSL			
Layer Thickness	mm	150	150	150			
Test Depth	mm	125	125	125			
Field Wet Density	t/m^3	1.91	1.89	1.87			
Field Moisture Content	%	24.1	23.8	23.1			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	0.0	0.0	0.0			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.93	1.91	1.89			
Optimum Moisture Content	%	22.5	22	21.5			
Moisture Ratio	%	107	108	107.5			
Moisture Variation from OMC	%	2.0 Wetter	2.0 Wetter	2.0 Wetter			
Density Ratio	%	99.0	99.0	99.0			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI06)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory:

David Burns

Date: 30/03/2022

N

Test Location



PROJECT: Newhaven Estate – Stage 15 (Level 1)	**CLIENT:** BMD Urban	**DATE:** 28/03/2022	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION: Tarneit	**PROJECT No:** 1120 0303-1 (SI06)	**SITE PLAN SKETCH—NOT TO SCALE**	

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client: BMD Urban **Job No:** BMD2032

Project: Newhaven Estate - Stage 15 (Level 1) **Report:** 7

Location: Tarneit

Sample No		19	20	21			
Date Tested		29/03/2022	29/03/2022	29/03/2022			
Time Tested		PM	PM	PM			
Test Location		Refer to Plan	Refer to Plan	Refer to Plan			
Level/Layer		FSL	FSL	FSL			
Layer Thickness	mm	150	150	150			
Test Depth	mm	125	125	125			
Field Wet Density	t/m^3	1.85	1.88	1.83			
Field Moisture Content	%	25.2	26.1	24.8			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	0.0	0.0	0.0			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.87	1.90	1.85			
Optimum Moisture Content	%	26	26.5	25			
Moisture Ratio	%	97	98.5	99			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	-0.5 Drier			
Density Ratio	%	99.0	99.0	99.0			

Specification: 98% STD **Test Selection:** N/A

Notes: Ref : 1120 0303-1 (SI07)

Test Method AS1289 5.8.1, 5.7.1, 2.1.1, 1.1 **Sampling Method:** AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory: David Burns

Date: 31/03/2022

PROJECT:	CLIENT:	DATE:	
Newhaven Estate – Stage 15 (Level 1)	BMD Urban	29/03/2022	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
LOCATION:	PROJECT No:		
Tarneit	1120 0303-1 (SI07)	SITE PLAN SKETCH—NOT TO SCALE	

A&Y ASSOCIATES
GEOTECHNICAL ENGINEERING CONSULTANTS

Field Density Test Results
AS1289.5.7.1

A & Y Associates Pty Ltd
5/16 Network Drive
Truganina VIC 3029
PH: 0400 413 531
info@ayassociates.com.au

Client:	BMD Urban			**Job No:**	BMD2032	
Project:	Newhaven Estate - Stage 15 (Level 1)			**Report:**	8	
Location:	Tarneit					

Sample No		22	23	24			
Date Tested		4/04/2022	4/04/2022	4/04/2022			
Time Tested		PM	PM	PM			
Test Location		Refer to Plan	Refer to Plan	Refer to Plan			
Level/Layer		FSL	FSL	FSL			
Layer Thickness	mm	200	200	200			
Test Depth	mm	175	175	175			
Field Wet Density	t/m^3	1.89	1.92	1.88			
Field Moisture Content	%	22.1	26.8	22.3			
Material:		Site Derived Clay Fill	Site Derived Clay Fill	Site Derived Clay Fill			
Oversize Material	WET, %	0.0	0.0	0.0			
Sieve Size	mm	19	19	19			
Peak Converted Wet Density	t/m^3	1.91	1.91	1.90			
Optimum Moisture Content	%	23	27.5	22.5			
Moisture Ratio	%	96	97.5	99			
Moisture Variation from OMC	%	-0.5 Drier	-0.5 Drier	-0.5 Drier			
Density Ratio	%	99.0	101.0	99.0			

Specification:	98% STD	**Test Selection:**	N/A
Notes:	Ref : 1120 0303-1 (SI08)		
Test Method	AS1289 5.8.1, 5.7.1, 2.1.1, 1.1	**Sampling Method:**	AS 1289 1.2.1 6.4(b)

NATA
WORLD RECOGNISED ACCREDITATION

NATA Accredited Laboratory No. 20172

Accreditation for compliance with ISO/IEC 17025 - Testing

The results of tests, calibrations and/or measurements included in this document, are traceable to Australian / National Standards

Approved Signatory: David Burns

Date: 13/04/2022

Test Location

PROJECT:	CLIENT:	DATE:	A&Y ASSOCIATES GEOTECHNICAL ENGINEERING CONSULTANTS
Newhaven Estate – Stage 15 (Level 1)	BMD Urban	04/04/2022	
LOCATION:	PROJECT No:	SITE PLAN SKETCH—NOT TO SCALE	
Tarneit	1120 0303-1 (SI08)		